


### EBMUD's Wet Weather Program, NPDES Permit and TSO



March 6, 2007

### **EBMUD Wastewater Service Area**



• Serves 9 cities and communities with a population of approximately 650,000

- Alameda
- Albany
- Berkeley
- Emeryville
- Oakland
- Piedmont
- Stege Sanitary District (El Cerrito, Kensington & part of Richmond)

#### EBMUD collects and treats wastewater

- 2900 miles of sewers (community owned)
- 30 miles of interceptors
- 14 pump stations
- Main Wastewater Treatment Plant

#### В

### Wet Weather Flow

- Pipes and manholes overflow
- Flow in pipes increases.
- Water enters sewer system through improper connections (Inflow)
- Water enters faulty joints and defects in communities' pipes and private laterals (Infiltration)
- Ground gets saturated
- It rains.

### В

# Inception of East Bay Wet Weather Program

- Beginning in 1976, stakeholders recognized need to get raw sewage off the streets
- Considerations included:
  - protection of human health
  - protection of the bay
  - technical feasibility
  - financial impact to rate payers
  - regulatory issues

### EBMUD

# **Program Planning**

- Time Frame: 1975 thru 1987
- Overall Cost: \$18 million (Local Funds and State Grants)

### Planning Reports:

- The Control of Wet Weather Overflows and Bypasses (1975)
- Wet Weather Facilities Plan (1980)
- East Bay I/I Study Manual for Cost-Effectiveness Analysis (1981)
- Local Effect Monitoring (LEM) Study (1982)
- Sewer System Evaluation Study (SSES) (1986)
- Wet Weather Facilities Plan Update (1985)
- EIR for I/I Correction Program (1986)
- EIR for District's Wet Weather Program (1986)
- LEM Program Update (1986)
- Predesign Report (1986)
- Final Cost Effectiveness Analysis Update for I/I Correction Program (1987)
- Project Report for MWWTP and Interceptors (1987)

## Approach

- EPA, SWRCB and RWQCB were actively involved, including program approval from inception through design to the present
  - Page 4 24 of current Basin Plan
  - District and Community NPDES permits
  - June 1986 letter from EPA Key Document
  - EIR processes
- Used hydraulic modeling of entire system to assess alternatives
- Alternatives included storage, treatment/discharge, and provision for overflows from storage and interceptors when storms exceeded design storm

# **Key Findings from Planning Work**

### Recommended two programs:

- Wet Weather Flow Storage and Treatment - responsibility of EBMUD
- Infiltration/Inflow Control -responsibility of collection agencies

# Wet Weather Program Elements

### EBMUD Program


- Spent \$325 million on Wet Weather Program
- Constructed 3 wet weather facilities, 2 wet weather interceptors, and system storage and pumping facilities
- Treatment facilities designed to address major public health concern
- Projects completed in 1998
- Communities' Program
  - Spent \$335 million on I/I Correction Program
  - Rehabilitating collection systems
    Approximately 80% of projects completed
  - Constructing relief sewers
    - Approximately 88% of projects completed



#### OAKPORT PEAK WET WEATHER TREATMENT FACILITY

#### **IN SERVICE SINCE 1990**

Design Flow: 158 MGD Storage: 3 MG Treatment: Sedimentation, Chlorination, Dechlorination



BMUD



PT. ISABEL PEAK WET WEATHER TREATMENT FACILITY

IN SERVICE SINCE 1993



Design Flow: 100 MGD Storage: 3 MG Treatment: Screening, Sedimentation, Chlorination, Dechlorination



#### SAN ANTONIO CREEK PEAK WET WEATHER TREATMENT FACILITY

IN SERVICE SINCE 1996



Design Flow: 51 MGD Treatment: Screening, Chlorination, Dechlorination






# **EBMUD Wet Weather Program Results**

	Before	After
Treatment Capacity	290 MGD	724 MGD*
Storage	0	18 MG
Untreated overflow events per year	Approx. 10	0.20

\* 415 MGD at MWWTP and 309 MGD at wet weather facilities

### Total Volume of Discharge from MWWTP vs. from Wet Weather Treatment Facilities for Period 1998-2005



25% of the money that EBMUD collects for wastewater services is spent on these infrequently operated facilities.

#### В

# **Current Permit Renewal Process**

- July 2002: Applied for renewal
- Fall 2003: Notified by RWQCB that development of new permit started
- January 2004: Started meeting with stakeholders to develop permit
  - EPA
  - RWQCB
  - Communities
- August 2004: Draft permit and TSO issued for public comment
- January through September 2005: Negotiations with RWQCB and NGOs in response to comments by NGOs and EPA Region 9 on draft permit and TSO

### Sec.

## **2005 Permit and TSO**

- Permit and TSO issued September 2005
- TSO mandates six studies to identify the conditions and requirements that will be put in next permit
- \$3.3 million in contracts have been executed to provide needed technical and cost information

# **TSO Study Investigations**

- 1) Treatment alternatives for the wet weather facilities
- 2) Storage and transport alternatives
- 3) Inflow and infiltration program enhancements
- 4) One-system permit model
- 5) Applicability of provisions in the SIP and CTR for addressing pollutants of concern
- 6) Offset projects for reducing discharges of pollutants of concern

### ЕВМИВ

# Challenges

- How to apply secondary standards
- Technical feasibility of possible alternatives
- Addressing the problem reducing peak flows
- Regional/satellite structure
- Understanding and managing financial impact




### **Financial Effects of Draft Order**

- The existing facilities which have not yet been fully paid for – would have to be dramatically modified or even removed
- The cost for EBMUD to define and apply secondary treatment standards at the wet weather facilities is estimated at \$1.9 billion.
- Additional costs are expected if other elements of the draft order are adopted.
- The effect on East Bay customers' wastewater rates would be dramatic.



### **Impact on Customer Rates**



# Summary and Conclusions

- The permit and TSO are the latest steps in addressing a difficult problem
  - 3 decades of analysis, planning and implementation
  - Hundreds of millions of dollars
  - Historical process supported by EPA, SWRCB, RWQCB, EBMUD and the communities
  - Plan has been working Dramatic reductions in the frequency and impacts of discharges
- All TSO elements are in full swing
  - Blue ribbon panel: EPA, RWQCB, EBMUD, NGOs, communities, League of Women Voters, business sector and scientific community
  - TSO process will result in identifying the most costeffective long term plan
  - The TSO studies lay the groundwork for the next permit round



# Summary and Conclusions (cont'd)

- SWRCB has discretion to allow the process to go forward
- SWRCB should exercise that discretion
- RWQCB could open the permit to correct factual errors