



WATER & WASTEWATER
 MUNICIPAL INFRASTRUCTURE
 LAND DEVELOPMENT
 AGRICULTURAL SERVICES
 DAIRY SERVICES
 LAND SURVEYING & GIS
 PLANNING & ENVIRONMENTAL
 DISTRICT MANAGEMENT

286 W. Cromwell Avenue
 Fresno, CA 93711-6168
 559 449-2700
 FAX 559 449-2715

JUL 28 2008

July 25, 2008

California Regional Water Quality Control Board
 Central Valley Region
 1685 "E" Street
 Fresno, CA 93706-2020

Attention: W. Dale Harvey, P.E., Senior Engineer

Subject: Malaga County Water District (MCWD)
 Order No. R5-2008-0033, NPDES No. CA 0084239
 Treatment and Disposal Capacity Study

Dear Mr. Harvey:

As required, please find attached an evaluation of the Treatment and Disposal Capacity of the facilities as required by Section 3.a. of the Cease and Desist Order.

Please contact me if you have any questions or if you require additional information.

Sincerely,

Michael G. Taylor, P.E.

MGT

Enclosure

cc: Malaga County Water District, Russ Holcomb, General Manager
 Fresno Irrigation District (FID), Lawrence Kimura
 2008 MCWD – RWQCB Correspondence File

Tech Rpts copy

MALAGA COUNTY WATER DISTRICT

Study Evaluating Treatment And Disposal Facilities

July 2008

Prepared for:

RWQCB

Prepared by:

Provost & Pritchard Engineering Group, Inc.
Fresno, California

COPYRIGHT 2008 by PROVOST & PRITCHARD ENGINEERING GROUP, INC.
ALL RIGHTS RESERVED

Provost & Pritchard Engineering Group, Inc. expressly reserves its common law copyright and other applicable property rights to this document. This document is not to be reproduced, changed, or copied in any form or manner whatsoever, nor are they to be assigned to a third party without first obtaining the written permission and consent of Provost & Pritchard Engineering Group, Inc. In the event of unauthorized reuse of the information contained herein by a third party, the third party shall hold the firm of Provost & Pritchard Engineering Group, Inc. harmless, and shall bear the cost of Provost & Pritchard Engineering Group, Inc.'s legal fees associated with defending and enforcing these rights.

TABLE OF CONTENTS

1	FLOWRATE AND CHARACTERISTICS	1
1.1	Existing Flowrate and Characteristics	1
1.2	Future Flowrate and Characteristics.....	1
2	TREATMENT FACILITIES.....	2
2.1	Design Criteria.....	2
2.2	Evaluation of Treatment Components	2
2.3	Headworks	2
2.4	Barminutor.....	3
2.5	Dissolved Air Floatation (DAF) Clarifier.....	3
2.6	Activated Sludge	3
2.7	Secondary Clarifiers	4
2.8	Sludge Digestion	5
2.9	Tertiary Filter	5
3	DISPOSAL FACILITIES	6
3.1	Background	6
3.2	Disposal Pond Requirements	7
3.3	Disposal Alternatives	7
3.4	Reclamation Alternatives.....	9
4	SUMMARY	12
4.1	Short Term	12
4.2	Long Term.....	12

TABLES

1	MCWD Flowrates
2	Property within Sphere of Influence
3	MCWD Future Flowrates
4	Percolation Rate Estimates in 2007
5	0.8 MGD Water Balance, Average Year Rainfall
6	0.8 MGD Water Balance, 100 Year Rainfall
7	1.2 MGD Water Balance, Average Year Rainfall
8	1.2 MGD Water Balance, 100 Year Rainfall
9	1.65 MGD Water Balance, Average Year Rainfall
10	1.65 MGD Water Balance, 100 Year Rainfall
11	Pond Acres needed to offset 0.45 MGD Canal Discharge
12	Potential Disposal Sites

FIGURES

- 1 Zoning within the Sphere of Influence
- 2 Potential Disposal Sites
- 3 Preliminary Alignment of Transmission Main
- 4 Preliminary Profile of Transmission Main
- 5 Preliminary Typical Pond Configuration
- 6 ADM and Calpine Property
- 7 Community Park Property
- 8 Konkel School Property
- 9 PPG Property
- 10 Rio Bravo Property
- 11 Summary of Short Term Improvement Schedule

APPENDIX

- A Design Criteria Summary
- B Master Plan of Wastewater Treatment Facilities
- C Preliminary Opinion of Cost for Disposal Facilities

1 FLOWRATE AND CHARACTERISTICS

1.1 Existing Flowrate and Characteristics

- A. The present flowrate received at the wastewater facilities is summarized in Table 1. It is noted that the facilities periodically receive high flows. For example, the District received average monthly flows in excess of 0.9 mgd from July through September of 2005 and from June through September in 2007. The District has received high flows again in the summer of 2008. The source of those flows is not yet determined, although they may due in part to high source water electroconductivity and the resulting impact to boiler blowdown generation from the industrial connections.
- B. It is noted that the flowrates reported include a recirculation flowrate estimated to be between 100,000 and 200,000 gpd from the grit wash tank. Existing influent characteristics are typically approximately 200 mg/l BOD₅ and approximately 200 mg/l TSS as reported to the RWQCB. It is noted that the influent characteristics are sampled when the grit wash recirculation is active. The impact of this recirculated flowrate to the characteristics is not known. Future samples will be obtained without the influence of the recirculated flows.

1.2 Future Flowrate and Characteristics

- A. The Waste Discharge Requirements are intended to be applied to a facility receiving up to 1.2 mgd. The existing average monthly flowrate received by the facilities ranged from 0.746 mgd to 1.020 mgd in 2007. Land use of property within the sphere of influence of the District, yet not connected to the sewer system is summarized in Table 2. Zoning within the sphere of Influence is shown in Figure 1.
- B. Based on previous growth rates in the Malaga County Water District, an anticipated increase of sewage received at the treatment facilities is summarized in Table 3. The growth rate is based on the average monthly flowrate increase between 1990 and 2007 (0.011 mgd increase per year). The ultimate flowrate for the treatment plant is unknown due to the extreme range of flows that could be attributed to the industrial land uses in the District.

2 TREATMENT FACILITIES

2.1 Design Criteria

- A. Design criteria for the wastewater treatment and disposal facilities are summarized on Plan Sheet 15 of 62 (1999) in the Appendix A.
- B. Specific requirements that require compliance are as follows:
- Average monthly electroconductivity (Ec) 500 μ mhos/cm greater than source water, or 1,000 μ mhos/cm, whichever is more stringent.
 - Chloride of 175 mg/l
- C. Tertiary effluent
- BOD₅ of 10 mg/l
 - TSS of 10/mg/l
 - Ammonia Nitrogen of 1.3 mg/l (as N) until May 2010
 - Ammonia Nitrogen of 0.4 mg/l (as N) after May 19, 2010
 - Boron of non-detect
 - Turbidity of 2 NTU
 - Total Coliform of 2.2 MPN/100 ml as a 7 day median

2.2 Evaluation of Treatment Components

2.3 Headworks

- A. The influent screw pumps have a capacity of 1,100 gpm each. The existing screw pumps have a capacity that is sufficient to meet existing and future demands. The existing screw pumps are in need of repair to the flights to maintain the pumping capacity.
- B. The existing headworks includes a grit removal facility. There is a continuous recirculation of a portion of the wastewater that is not metered separately. The MCWD is in the process of installing a new flowmeter to enable monitoring of the recirculated flow.
1. Short-Term measures: repair flights of screw pumps within 12 months.
Construct grit chamber flow measurement within four 4 months.
 2. Long-Term measures: maintain a fund for the purpose of maintaining and replacing the screw pumps as needed.

2.4 Barminutor

The barminutor has a capacity of 1.2 mgd. The barminutor is sufficient to meet anticipated demands through 2028. The barminutor is presently out of service for maintenance and is expected to be placed into operation in August 2008.

2.5 Dissolved Air Floatation (DAF) Clarifier

- A. The existing DAF has been out of service for several years due to the discovery of leaks from the structure that resulted in the surfacing of untreated effluent. The entire interior surface of the DAF was recently re-coated and sealed. Leaks continue to come from the structure and are now limited to two (2) 12 inch diameter lines that feed the DAF and are located underneath the structure. The workplan to bring the DAF into service is as follows:

<u>Task</u>	<u>Timeline</u>
Video review of existing pipeline	June 2008
Physical confirmation of as-built Conditions and dimensions	July 2008
Initiate construction of improvements	October 2008
Complete construction, perform leak testing	December 2008
Return DAF to service	January 2008

- B. The capacity of the DAF is estimated to be 1.2 mgd. A long term plan for expansion of the primary sedimentation facilities is to construct a second DAF as shown in Appendix B. Presently, the lack of the DAF has not compromised the ability of the facilities to meet Waste Discharge Requirements.

1. Short term measures: Repair/replace influent pipelines and place the DAF back into service by January 2009.
2. Long term measures: Construct a second DAF with a capacity of 1.65 at such time that the average influent flowrate reaches 1.10 mgd.

2.6 Activated Sludge

- A. The capacity of the activated sludge tanks is 1.20 mgd. The activated sludge system is dependent upon the three existing blowers that supply 1,500 of cfm to the fine bubble diffuser system. The existing tank volume, detention time, and oxygen supply are sufficient to meet the new discharge requirements for BOD and TSS until the flowrate of 1.2 mgd is reached. A summary of the design criteria for the activated sludge units is contained in Appendix A. Performance of

the activated sludge facilities regarding ammonia is not yet verified. Monitoring of nitrogen forms within the effluent has recently been initiated. Enhancements that may be implemented at the activated sludge facilities may include:

1. Recirculation of RAS to the headworks,
2. Installation of fixed media beds within the existing activated sludge tanks, or
3. Creation of anoxic zones within the activated sludge tanks by restricting air flow in specific locations.

A workplan to investigate the activated sludge units is as follows:

<u>Task</u>	<u>Timeline</u>
Evaluate the existing units and air flow regarding nitrification and denitrification	July-August 2008
Recommend improvements or modifications to present operations (short-term and long-term)	September 2008
Implement short-term measures (if necessary)	December 2008

B. A long-term plan for expansion of the activated sludge units is to install two (2) additional blowers and construct one (1) additional activated sludge tank as shown in Appendix B.

1. Short-term measures: Complete the workplan to investigate the nitrification capabilities of the existing facilities. Implement recommendations of the short-term workplan by December 2008.
2. Long-term measures: Expand the activated sludge tank and associated blowers to a capacity of 1.65 mgd at such time the average monthly flowrate is 1.1 mgd.

2.7 Secondary Clarifiers

A. Although three (3) secondary clarifier tanks are located within the treatment facilities, only one (1) clarifier is in operation. The capacity of the clarifier is 823,000 gpd. The facilities lack redundancy and the ability to meet periodic high influent flowrates. The overall capacity of the three (3) secondary clarifiers is 1.65 mgd (one clarifier held in reserve for redundancy). The workplan to bring a second clarifier into service is as follows:

<u>Task</u>	<u>Timeline</u>
Determine availability and cost of clarifier drive mechanism, chain and flights	June-July 2008
Initiate contract to install necessary components in the second clarifier	September 2008
Review necessary structural repairs to the third clarifier tank – cold joint between structures	August-Sept. 2008
Initiate repairs to the third clarifier structure	April 2009
Construct mechanical components in third clarifier	June 2009
1. <u>Short-term measures</u> : Proceed with workplan as outlined above.	
2. <u>Long-term measures</u> : TBD	

2.8 Sludge Digestion

- A. The existing sludge digesters have a capacity of 1.2 mgd. The operation of the sludge digesters is proceeding as required. No specific upgrades or improvements are needed at this time.
- B. The sludge thickener is in need of repair to the chain and flight mechanism. The thickness is out of service at the present. District staff is proceeding with initiating the necessary purchase of replacement components.
 1. Short-term measures: Repair sludge thickener by September 2008. Construct lining of the third sludge drying bed in 2009.
 2. Long-term measures: TBD

2.9 Tertiary Filter

- A. The existing tertiary filter has a capacity of 0.45 mgd, which is equivalent to the existing permit for discharge. The Fresno Irrigation District (FID) has requested that the MCWD initiate actions to become independent of canal discharge. Therefore, immediate expansion of the Tertiary filter is not warranted. Previous evaluations recommended an expansion of the tertiary filtration system to at least 0.7 mgd to alleviate pressure from the disposal ponds.
- B. The MCWD is presently designing an ultraviolet (UV) light disinfection system to replace the existing chlorination/dechlorination facilities and achieve more consistency in meeting the electroconductivity limits. The UV system will allow the facilities to meet the new requirements for bromoform, chlorodibromomethane, and dichlorobromomethane.

1. Short-term measures: Complete the improvements necessary to convert to UV disinfection.
2. Long-term measures: TBD

3 DISPOSAL FACILITIES

3.1 Background

- A. Provost & Pritchard Engineering Group, Inc. was authorized by the Board of Directors to evaluate disposal pond expansion alternatives for wastewater treatment plant design flows of 1.2 MGD and 1.65 MGD (future), evaluate potential disposal sites and estimate capital costs associated with the additional disposal facilities.
- B. Additional disposal capacity is of critical need to address both present flow rates and design capacity flows for the wastewater treatment plant. In addition the FID has notified the District of the need to become independent of the discharge to the Central Canal.

The California Regional Water Quality Control Board (RWQCB) Cease and Desist Order issued March 14, 2008 requires a study evaluating the current disposal capacity and addressing additional short term and long term disposal capacity be submitted by District within 90 days of permit adoption.

- C. The District will also evaluate reclamation of the treated effluent and reclamation of industrial effluent within the next 45 days. The wastewater treatment plant site has 23.24 acres of disposal ponds and no vacant property for additional ponds. Wastewater treatment plant data for 2007 was studied and determined that percolation rates remain at no greater than 0.6 inches per day. The 2007 study confirmed the percolation data previously reviewed in 2005. Calculations for the 2007 study can be found in Table 4. Decreasing percolation and increasing flow rates have caused pond freeboard to be chronically in violation of the WDR requirements over the last few years. Tertiary treatment and disposal to the Central Canal, was implemented in 2001 to relieve pond loading and allow for pond maintenance, however increased in flow rates to the wastewater treatment plant have offset the additional discharge capacity.
- D. Due to periodic high flow rates pond maintenance to improve percolation has not been performed. It is anticipated that maintenance of the existing ponds would initially increase percolation to 1.0 inches per day. Regular pond maintenance would keep percolation rates at higher levels and remove solids and silt build up that cause reduced percolation rates.
- E. Actions to enhance disposal capacity or to decrease flows at the treatment facilities are critical in the next 6 to 9 months.

3.2 Disposal Pond Requirements

- A. Water balances have been prepared to evaluate the disposal requirements for the current wastewater treatment flowrates, design capacity of 1.2 MGD and the ultimate wastewater treatment capacity of 1.65 MGD. Average year and 100 year rainfall scenarios were evaluated for each flowrate in Tables 5 through 10.

The total pond required disposal pond capacity required was found to be:

Existing Acres	23.24 ac
0.8 MGD ¹	36.50 ac
1.2 MGD ²	50.50 ac
1.65 MGD ³	66.20 ac

1. Present Flows (approximate)
2. Current WWTP Design Capacity
3. Ultimate WWTP Design Capacity

- B. To prepare conservative estimates of required disposal areas, it was assumed that at any given time 23.24 acres of ponds would have reduced percolation rates of 0.6 inches per day (ponds requiring maintenance) and the remaining ponds would have percolation rates of up to 1.0 inches per day (ponds recently maintained).

Additional acres of disposal ponds needed:

0.8 MGD - Present Flowrate	
Total Required	36.50 ac
Existing Disposal Ponds	<u>23.24 ac</u>
Additional Ponds Required	13.26 ac

1.2 MGD – Design Capacity	
Total Required	50.50 ac
Existing Disposal Ponds	<u>23.24 ac</u>
Additional Ponds Required	27.26 ac

1.65 MGD – Ultimate Capacity	
Total Required	66.20 ac
Existing Disposal Ponds	<u>23.24 ac</u>
Additional Ponds Required	42.96 ac

- C. A water balance prepared to evaluate the pond acreage required to offset the 0.45 mgd discharge to the Central Canal, suggests that 15 acres of ponds would be required (See Table 11).

3.3 Disposal Alternatives

- A. Six (6) potential disposals sites have been identified for the purposes of this preliminary report. All of the sites are south of the wastewater treatment plant near the intersection of Malaga Avenue and Maple Avenue. The area is primarily

agricultural with some single family residences on parcels that range in size from 1 to 18 acres.

- B. Table 12 lists the parcel number, property owner, total parcel acreage and pond acreage that could be provided by each site.

The proposed disposal sites have been evaluated with consideration for the following factors:

1. Size and configuration of property
2. Distance from WWTP
3. Existing site conditions
4. Williamson Act –non-agricultural preserve

- C. Additional factors considered when considering possible disposal sites are the relative locations of Highway 99, the Central Canal and the Southern Pacific Railroad tracks. Traffic volume at the intersection of Maple and Central and the location of existing utilities, irrigation structures, and ditches also must be considered in evaluating potential disposal sites. A pump station and a transmission main would be required to convey treated wastewater to any disposal site.
- D. Figure 2 shows the vicinity of the WWTP and the APN numbers of parcels in the area being considered for potential disposal sites. Only one parcel, APN 330 031 45S, is large enough to provide all required disposal capacity for the ultimate treatment plant design capacity of 1.65 MGD. Portions of that parcel or smaller parcels could be combined to provide required disposal capacity as flowrates to the wastewater treatment plant increase.
- E. If property in the vicinity of Maple and Malaga Avenues is acquired, the treated effluent would require a transmission main along Maple Avenue or along an easement parallel to the railroad approximately ¼ mile west of Maple Avenue. A preliminary alignment of the transmission main is included in Figures 4,5 A, and 5B. It is noted that if the transmission main is to follow Maple Avenue, an easement with Parnegian may be required due to the various existing and proposed utilities in Maple Avenue and the high volume of truck traffic at Maple and Central Avenue.
- F. The configuration of ponds on any site will be dependent on site conditions, size and location. Figure 3 is an example of a typical pond configuration on one of the potential sites.
- G. A preliminary estimate of capital costs for disposal facilities located on APN 330 031 42S is included in Appendix C.

1. Short-term measures:

Within 30 days:

- a. Conduct additional property research, contact property owners to identify potential willing sellers. Consider hiring a consultant to assist with property acquisition.
- b. Drain Pond No. 5 during the summer of 2008. Allow it to dry for 2-3 weeks then scrape the bottom and then deep rip the bottom.
- c. Consider a moratorium on any new connections or expansion of existing connections until disposal facilities are expanded.

Within 60 days:

- a. Enter into negotiations for purchase or long term lease of a property for disposal ponds. Prepare environmental documents for the proposed project.
- b. Determine financial means to construct the project.
- c. Prepare a timeline for additional disposal capacity improvements.

2. Long-term measures:

- a. Acquire approximately 30 acres of additional property for the construction of percolation/evaporation ponds.

3.4 Reclamation Alternatives

- A. In addition to reviewing alternatives of additional property for the purpose of percolation/evaporation ponds, there may be viable alternatives for reclamation within the District. Alternatives may include:
 1. Reclamation of treated effluent to Caltrans landscaping
 2. Reclamation of treated effluent for agricultural purposes
- B. The MCWD has contacted Caltrans regarding a) the willingness of Caltrans to receive treated effluent, b) the potential volume of water that may be reclaimed, and c) the cost of the reclamation.
- C. Discussions with Caltrans in November of 2007 indicated a willingness to receive the treated effluent in concept. Concerns expressed by Caltrans included the suitability of existing landscapes to the effluent, the need to construct a dual feed system in the event reclaimed water was not available, the ability of Caltrans to maintain the inspection system and landscaping, training of Caltrans personnel in handling treated effluent. Malaga CWD presently provides Caltrans with water for landscaping. Unfortunately, the total water used during the peak month of

2007 was only 7,230 gal/d. The alternative to irrigate Caltrans landscaping, therefore, is not viable to alleviate disposal restrictions.

- D. Agricultural property in the vicinity of the wastewater treatment plant is presently irrigated by private wells and supplemented by FID. The present discharge by MCWD to the FID Central Canal provides approximately 1.3 acre-feet of water per day to the canal. Agricultural properties in the vicinity of the treatment plant are not willing to modify irrigation practices for the relatively small amount of irrigation water.

- E. There exists, several large industries within Malaga County Water District east of State Route 99. These industries discharge industrial boiler blow down water in addition to other waste streams. There exists a potential to construct a separate satellite treatment facility for boiler blow down water that may be treated and disposed of (percolation/evaporation ponds) on the east side of State Route 99. The industrial sites for PPG and Rio Bravo are adjacent to each other. These two sites generate a significant amount of the boiler blowdown received by MCWD. The option of collecting those two waste streams, providing necessary secondary treatment and then disposal in compliance with new Waste Discharge Requirements of property to be obtained by the MCWD would be explored. The alternative reduces the amount of additional property required west of State Route 99.
 - 1. Short-term measures:
 - a. Contact Calpine and PPG regarding the willingness to sell property to MCWD.
 - 2. Long-term measures:
 - a. Purchase property from PPG, Calpine, and/or ADM.
 - b. Construct new disposal ponds
 - c. Construct a satellite treatment plant
 - d. Construct a separate collection system for boiler blowdown

- F. There exists potential to separate the boiler blowdown water as a separate waste stream, provide separate treatment facilities, and then reclaim the effluent for industrial or irrigation purposes.

- G. Potential reclamation sources or disposal sites are shown on Figures 6-10. The sites are listed as follows:

<u>Figure</u>	<u>Site</u>
6	ADM and Calpine
7	Community Park Property
8	Konkel School Property
9	PPG Property
10	Rio Bravo Property

- H. The reclamation sites offer the opportunity to reduce the influent flowrate to the treatment facilities by capturing the boiler blowdown water. If necessary, water from the District wells could be used to reduce the Ec of the reclaimed water to levels acceptable for landscape irrigation.
- I. Each acre of lawn that could be irrigated may reduce the amount of sewage received at the treatment facilities by approximately 250 gal/d in an average rainfall year.
1. Short-term measures:
 - a. Determine the suitability of a typical lawn to Ec levels of 800 $\mu\text{mhos/cm}$
 - b. Contact the Department of Public Health regarding the potential of irrigation of tertiary effluent on private sites
 - c. Contact PPG, Rio Bravo, ADM regarding the potential of irrigating or other reclamation with boiler blowdown water
 - d. Contact representatives of the Konkel School regarding the potential or irrigation of lawn with boiler blowdown
 2. Long-term measures:
 - a. Obtain Reclamation Permits from the Department of Public Health for reclamation.
 - b. Construct a separate collection system, treatment plant and distribution system for irrigation of boiler blowdown.

4 SUMMARY

4.1 Short Term

A. Immediate deficiencies at the treatment facilities are:

1. Influent flow measurement - complete
2. DAF Clarifier - complete
3. Secondary Clarifiers - one fixed - one has landing in place
4. Sludge Thickener - complete
5. UV Disinfection - complete

B. The MCWD has identified a plan to install grit recirculation flow measurement in 2008, return to DAF to service in 2008, install improvements to an additional secondary clarifier in 2008, and repair the chain and flight mechanism of the sludge thickener. The ultraviolet light disinfection system is also scheduled for construction in 2008.

C. The MCWD continues to pursue means to reduce electroconductivity within the influent flowrate through pretreatment requirements.

D. The facilities presently meet ammonia requirements however additional monitoring information is required prior to recommending additional improvements.

E. Disposal facilities are in critical need of expansion. Additional property acquisition and pond construction is critical.

F. A summary of the anticipated schedule for short term improvements is included as Figure 11.

4.2 Long Term

A. Master plan expansion of DAF and Activated Sludge Facilities are identified.

B. Future disposal alternatives are dependent upon the viability of reclamation proposal and the acquisition of additional disposal ponds.

TABLES

TABLE 1

MALAGA COUNTY WATER DISTRICT
 WASTEWATER TREATMENT PLANT
 MONITORING AND REPORTING PROGRAM NO. 2008-0033
 NPDES NO. CA 0084239

YEAR	0.8 of Permit Flow	AVERAGE FLOWRATE	JAN	FEB	MAR	APR	MAY	JUN	JUL	AUG	SEP	OCT	NOV	DEC
1990		0.677	0.660	0.667	0.694	0.610	0.688	0.709	0.652	0.664	0.679	0.726	0.741	0.632
1991		0.694	0.642	0.651	0.694	0.687	0.684	0.697	0.682	0.703	0.728	0.712	0.713	0.731
1992		0.735	0.727	0.741	0.735	0.681	0.679	0.740	0.753	0.768	0.743	0.768	0.756	0.729
1993		0.716	0.727	0.720	0.724	0.721	0.715	0.703	0.705	0.712	0.714	0.703	0.709	0.734
1994		0.724	0.748	0.739	0.743	0.743	0.745	0.740	0.739	0.737	0.731	0.722	0.669	0.636
1995		0.660	0.638	0.635	0.621	0.614	0.626	0.636	0.641	0.695	0.699	0.705	0.709	0.699
1996		0.688	0.671	0.680	0.676	0.690	0.690	0.689	0.692	0.691	0.686	0.694	0.696	0.705
1997	0.96	0.714	0.686	0.681	0.681	0.690	0.704	0.715	0.711	0.740	0.756	0.722	0.734	0.749
1998	0.96	0.745	0.744	0.743	0.737	0.772	0.755	0.756	0.738	0.775	0.740	0.739	0.706	0.738
1999	0.96	0.760	0.753	0.753	0.735	0.746	0.765	0.762	0.778	0.780	0.770	0.761	0.760	0.751
2000	0.96	0.772	0.723	0.744	0.738	0.754	0.783	0.767	0.772	0.808	0.770	0.770	0.797	0.810
2001	0.96	0.763	0.776	0.771	0.701	0.810	0.755	0.780	0.750	0.770	0.773	0.754	0.760	0.756
2002	0.96	0.748	0.742	0.750	0.737	0.748	0.745	0.737	0.746	0.740	0.755	0.750	0.747	0.763
2003	0.96	0.747	0.752	0.752	0.737	0.750	0.740	0.746	0.758	0.742	0.740	0.750	0.750	0.745
2004	0.96	0.746	0.760	0.737	0.722	0.717	0.734	0.760	0.750	0.750	0.770	0.740	0.778	0.750
2005	0.96	0.823	0.860	0.780	0.760	0.770	0.763	0.870	0.960	0.935	0.964	0.820	0.798	0.752
2006	0.96	0.788	0.740	0.740	0.760	0.744	0.757	0.806	0.849	0.882	0.803	0.820	0.746	0.763
2007	0.96	0.860	0.785	0.820	0.805	0.867	0.770	0.964	1.001	0.960	1.020	0.823	0.746	0.763
2008	0.96	0.355	0.990	0.840	0.760	0.760	0.909	0.000	0.000	0.000	0.000	0.000	0.000	0.000
2009	0.96	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
2010	0.96	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
2011	0.96	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
2012	0.96	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000
2013	0.96	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000	0.000

TABLE 2

Property within Sphere of Influence
Not Yet Connected to Community System

Land Use Zoning	Acres	Estimated Sewage Generation (gal/ac-d)	Future Sewage Contribution (gal/d)
AE-5	95.1	1,000	95,100
AL-20	738.4	1,000	738,400
C6	1.7	4,000	6,800
CM	0.8	4,000	3,200
M1	6.4	5,000	32,000
M3	405.4	5,000	2,027,000
O	14.3	100	1,430
RA	2.3	2,000	4,600
Total	1,264.4		2,908,530

TABLE 3

Future Flowrates

Year	Flowrate (mgd)
2007	0.862
2008	0.871
2013	0.926
2018	0.981
2023	1.036
2028	1.091
ultimate	To be determined

TABLE 4

Malaga County Water District
2007 Percolation Rate Estimates

Percolation Pond	Pond 1	Pond 2	Pond 3	Pond 4	Pond 5	Pond 6	Pond 7	Pond 8
Beginning Depth	4.09	4.59	4.92	4.84	4.84	4.50	4.84	4.75
Secondary Inflow Inflow ¹ (ft/yr)	25.37	25.37	25.37	25.37	25.37	25.37	25.37	25.37
Rainfall Inflow ² (ft/yr)	0.588	0.588	0.588	0.588	0.588	0.588	0.588	0.588
Evaporation ³ (ft/yr)	5.1375	5.1375	5.1375	5.1375	5.1375	5.1375	5.1375	5.1375
December 28, 2007	4.50	4.75	5.09	5.00	4.92	4.75	5.00	4.92
Percolation ⁴ (ft/yr)	20.41	20.66	20.65	20.66	20.74	20.57	20.66	20.65
Percolation Rate (ft/day)	0.056	0.057	0.057	0.057	0.057	0.056	0.057	0.057

Note:

1. Secondary inflow distributed evenly in all ponds.
2. Rainfall inflow based on 2007 rainfall data.
3. Evaporation based on WRCC average year pan evaporation x 0.75
4. Percolation = Beginning depth + Inflows - Evaporation - Ending Depth

Table 5
 Malaga County Water District
 Wastewater Treatment & Disposal Facilities
 0.8 MGD Capacity Wastewater Disposal - Average Year Rainfall Water Balance, Discharge and Storage

WWTF POND CALCULATIONS:

Month	Number of Days per Month	Average Yr. Rainfall ^{1/} (in/month)	Average Yr. Evaporation ^{3/} (in/month)	Discharge to canal			Effluent Produced (gal/month)	Effluent To Canal (gal/month)	Effluent to Ponds ^{16/} (gal/month)	Surface Rainfall ^{19/} (gal/month)	Surface Evaporation ^{20/} (gal/month)	Pond Percolation ^{21/} (gal/month)	Monthly Change in Storage ^{22/} (gal/month)	Required Storage ^{23/} (gal)
				0	MGD	gpd								
January	31	2.11	0.98				24,800,000	0	24,800,000	1,990,447	924,473	21,418,325	4,447,649	11,578,101
February	28	1.91	1.58				22,400,000	0	22,400,000	1,801,779	1,490,477	19,345,584	3,365,718	14,943,819
March	31	1.89	3.15				24,800,000	0	24,800,000	1,782,913	2,971,521	21,418,325	2,193,067	17,136,886
April	30	1.00	4.73				24,000,000	0	24,000,000	943,340	4,461,998	20,727,411	(246,069)	16,890,817
May	31	0.37	6.98				24,800,000	0	24,800,000	349,036	6,584,513	21,418,325	(2,853,802)	14,037,015
June	30	0.15	8.55				24,000,000	0	24,000,000	141,501	8,065,557	20,727,411	(4,651,467)	9,385,548
July	31	0.01	9.30				24,800,000	0	24,800,000	9,433	8,773,052	21,418,325	(5,381,954)	4,003,594
August	31	0.01	8.03				24,800,000	0	24,800,000	9,433	7,575,020	21,418,325	(4,183,912)	0*
September	30	0.17	5.93				24,000,000	0	24,000,000	160,368	5,594,006	20,727,411	(2,161,049)	0*
October	31	0.53	3.75				24,800,000	0	24,800,000	499,970	3,537,525	21,418,325	344,120	344,120
November	30	1.19	1.73				24,000,000	0	24,000,000	1,122,575	1,631,978	20,727,411	2,763,186	3,107,306
December	31	1.58	0.90				24,800,000	0	24,800,000	1,490,477	849,006	21,418,325	4,023,146	7,130,452
Total	365	10.92	55.61				282,000,000	0.0	282,000,000	10,301,272	52,459,138	252,183,503	-2,341,367	773.9

Total Area = 34.7 acres

6 ft deep

8 ft deep

Total (gal)

896.1

0.0

896.1

31.6

161.0

773.9

-2,341,367

1/ Rainfall Data per the Western Regional Climate Center.
 3/ Evaporation data per WPCCC X 0.75
 5/ Average Daily Effluent Production
 7/ Total wet area of the existing lagoons.
 19/ Surface Rainfall = Volume of Average-Year rainfall on the existing WWTF treatment and storage ponds and proposed storage ponds.
 20/ Surface Evaporation = Volume of effluent and rain water evaporating from the existing WWTF treatment and disposal ponds.
 21/ Pond Percolation = Volume of effluent and rain water percolating into the ground for existing ponds 1 through 8 plus additional proposed ponds.
 23/ Required Storage = Theoretical starting point Sept. 1st where pond storage starts at zero with monthly contributions.
 36/ Maximum Storage Needed = Peak end of month pond storage volume needed (gallons & ac-ft)
 37/ Storage Available from all ponds = Total volume of available storage.
 39/ Check Balance = Comparison of this value with 16/.

Maximum Required storage	17,136,886
Total Storage Available	83,066,052 gal
Extra Storage	65,929,166 gal
Total Effluent Production	292,000,000 gal
Total Effluent Exported	0 gal
Total Surface Rainfall	10,301,272 gal
Total Evaporation	52,459,136 gal
Total Percolation	252,183,503 gal
Effluent Applied to Crop	0 gal
Check Balance	294,341,367 gal



Table 6
 Malaga County Water District
 Wastewater Treatment & Disposal Facilities
 0.8 MGD Capacity Wastewater Disposal - 100 Year Rainfall Water Balance, Discharge and Storage

DATA:

Month	Number of Days per Month	100 Yr. Rainfall ^{1/} (in/month)	100 Yr. Evaporation ^{2/} (in/month)
January	31	5.14	0.90
February	28	3.70	1.46
March	31	4.53	2.09
April	30	2.76	3.71
May	31	0.01	6.21
June	30	0.31	6.85
July	31	0.00	8.14
August	31	0.00	6.99
September	30	1.10	4.68
October	31	1.58	3.09
November	30	3.16	1.20
December	31	1.59	0.85
Total	365	23.88	46.17

Total Area = 36.7 acres

Effluent Produced (gal/month)	Effluent To Canal (gal/month)	Effluent to Ponds ^{19/} (gal/month)	Surface Rainfall ^{19/} (gal/month)	Surface Evaporation ^{20/} (gal/month)	Pond Percolation ^{21/} (gal/month)	Monthly Change in Storage ^{22/} (gal/month)	Required Storage Capacity ^{23/} (gal)
24,800,000	0	24,800,000	5,127,913	897,884	23,101,890	5,928,139	12,154,893
22,400,000	0	22,400,000	3,691,300	1,456,567	20,866,224	3,768,509	15,923,402
24,800,000	0	24,800,000	4,519,348	2,085,085	23,101,890	4,132,373	20,055,775
24,000,000	0	24,000,000	2,753,510	3,701,276	22,356,668	695,666	20,751,341
24,800,000	0	24,800,000	9,976	6,195,397	23,101,890	(4,487,311)	16,264,030
24,000,000	0	24,000,000	309,271	6,833,892	22,356,668	(4,881,289)	11,382,741
24,800,000	0	24,800,000	0	8,120,859	23,101,890	(6,422,749)	4,959,992
24,800,000	0	24,800,000	1,097,413	4,688,995	22,356,668	(5,275,453)	0
24,000,000	0	24,000,000	1,576,285	3,082,734	23,101,890	(1,928,250)	0
24,800,000	0	24,800,000	3,152,569	1,197,178	22,356,668	191,661	191,661
24,000,000	0	24,000,000	1,586,261	848,001	23,101,890	3,598,723	3,790,384
24,800,000	0	24,800,000	23,823,846	46,061,431	272,006,126	2,436,370	6,226,754
292,000,000	0.0	292,000,000	73.1	141.4	834.8	-2,243,711	-6.9

* Start at 0 Stored September 1st

WWTF POND CALCULATIONS:

- 1/ Rainfall Data per the Western Regional Climate Center.
- 2/ Evaporation data per WRCC X 0.75
- 3/ Design Capacity Effluent Production
- 7/ Total existing wet area of the existing lagoons.
- 19/ Surface Rainfall = Volume of 100 Year rainfall on the existing WWTF treatment and storage ponds and proposed storage ponds.
- 20/ Surface Evaporation = Volume of effluent and rain water evaporating from the existing WWTF treatment and disposal ponds.
- 21/ Pond Percolation = Volume of effluent and rain water percolating into the ground for existing ponds 1 through 8 plus proposed additional ponds.
- 22/ Required Storage = Theoretical starting point Sept. 1st where pond storage starts at zero with monthly contributions.
- 36/ Maximum Storage Needed = Peak end of month pond storage volume needed (gallons & ac-ft).
- 37/ Storage Available from all ponds = Total volume of available storage.
- 39/ Check Balance = Comparison of this value with 16/.

Maximum Required storage	20,751,341
Total Storage Available ^{37/}	86,976,269 gal
Extra Storage ^{38/}	66,224,928 gal
Total Effluent Production ^{16/}	292,000,000 gal
Total Effluent Exported ^{17/}	0 gal
Total Surface Rainfall ^{19/}	23,823,846 gal
Total Evaporation ^{20/}	46,061,431 gal
Total Percolation ^{21/}	272,006,126 gal
Effluent Applied to Crop ^{28/}	0 gal
Check Balance ^{39/}	294,243,711 gal

Updated: 4/14/08
 Print Date: 7/25/08



Table 7
Malaga County Water District
Wastewater Treatment & Disposal Facilities
1.2 MGD Capacity Wastewater Disposal - Average Year Rainfall Water Balance, Discharge and Storage

WWTF POND CALCULATIONS:

Month	Number of Days per Month	Average Yr. Rainfall ^{1/} (in/month)	Average Yr. Evaporation ^{2/} (in/month)	Discharge to canal	0	MGD	Effluent Produced (gal/month)	Effluent To Canal (gal/month)	Effluent To Ponds ^{3/} (gal/month)	Surface Rainfall ^{19/} (gal/month)	Surface Evaporation ^{20/} (gal/month)	Pond Percolation ^{21/} (gal/month)	Monthly Change in Storage ^{22/} (gal/month)	Required Storage Capacity ^{23/} (gal)
January	31	2.11	0.98				37,200,000	0	37,200,000	2,735,289	1,270,419	32,361,502	6,303,368	16,670,036
February	28	1.91	1.58				33,600,000	0	33,600,000	2,476,020	2,048,226	29,229,744	4,798,050	21,468,086
March	31	1.89	3.15				37,200,000	0	37,200,000	2,450,093	4,083,489	32,361,502	3,205,102	24,673,188
April	30	1.00	4.73				36,000,000	0	36,000,000	1,296,346	6,131,715	31,317,583	(152,952)	24,520,236
May	31	0.37	6.98				37,200,000	0	37,200,000	479,648	9,048,493	32,361,502	(3,730,347)	20,789,889
June	30	0.15	8.55				36,000,000	0	36,000,000	194,452	11,083,756	31,317,583	(6,206,887)	14,583,002
July	31	0.01	9.30				37,200,000	0	37,200,000	12,963	12,056,015	32,361,502	(7,204,554)	7,378,448
August	31	0.01	8.03				37,200,000	0	37,200,000	12,963	10,409,656	32,361,502	(5,558,195)	1,820,253
September	30	0.17	5.93				36,000,000	0	36,000,000	220,379	7,687,330	31,317,583	(2,784,534)	0*
October	31	0.53	3.75				37,200,000	0	37,200,000	687,063	4,861,296	32,361,502	664,285	664,285
November	30	1.19	1.73				36,000,000	0	36,000,000	1,542,651	2,242,678	31,317,583	3,982,390	4,646,655
December	31	1.58	0.90				37,200,000	0	37,200,000	2,048,226	1,166,711	32,361,502	5,720,013	10,386,668
Total	365	10.92	55.61				438,000,000	0.0	438,000,000	14,156,093	72,889,761	381,030,580	-864,281	10,386,668

Total Area = 47.7 acres

Total (gal)

1,344.2

0.0

1,344.2

43.4

221.2

1,169.3

-964,281

3.0

September 1st

1/ Rainfall Data per the Western Regional Climate Center.
 2/ Evaporation data per WRCC X 0.75
 3/ Average Daily Effluent Production
 4/ Total wet area of the existing lagoons.
 19/ Surface Rainfall = Volume of Average-Year rainfall on the existing WWTF treatment and storage ponds and proposed storage ponds.
 20/ Surface Evaporation = Volume of effluent and rain water evaporating from the existing WWTF treatment and disposal ponds.
 21/ Pond Percolation = Volume of effluent and rain water percolating into the ground for existing ponds 1 through 8 plus additional proposed ponds.
 23/ Required Storage = Theoretical starting point Sept. 1st where pond storage starts at zero with monthly contributions.
 36/ Maximum Storage Needed = Peak end of month pond storage volume needed (gallons & ac-ft)
 37/ Storage Available from all ponds = Total volume of available storage.
 39/ Check Balance = Comparison of this value with 16/.

Maximum Required storage	24,673,188
Total Storage Available ^{32/}	108,482,485 gal
Extra Storage ^{38/}	83,809,277 gal
Total Effluent Production ^{16/}	438,000,000 gal
Total Effluent Exported ^{17/}	0 gal
Total Surface Rainfall ^{19/}	14,156,093 gal
Total Evaporation ^{20/}	72,089,784 gal
Total Percolation ^{21/}	381,030,590 gal
Effluent Applied to Crop ^{28/}	0 gal
Check Balance ^{39/}	438,964,281 gal

Updated: 4/14/08
 Print Date: 7/23/08



Table 8
 Malaga County Water District
 Wastewater Treatment & Disposal Facilities
 1.2 MGD Capacity Wastewater Disposal - 100 Year Rainfall Water Balance, Discharge and Storage

WWTFF POND CALCULATIONS:

Month	Number of Days per Month	100 Yr. Rainfall ^{1/} (in/month)	Evaporation ^{2/} (in/month)	Discharge to canal	0	MGD	Daily Effluent Production ^{3/} = 1,200,000 gpd		Pond Wet Area ^{4/} = 23.24 acres	Pond Storage = 185.9 ac-ft	Pond Percolation Rate = 0.60 in/day	8 ft deep	Effluent Produced (gal/month)	Effluent To Canal (gal/month)	Effluent to Ponds ^{16/} (gal/month)	Surface Rainfall ^{19/} (gal/month)	Surface Evaporation ^{20/} (gal/month)	Pond Percolation ^{21/} (gal/month)	Monthly Change in Storage ^{22/} (gal/month)	Required Storage Capacity ^{23/} (gal)
							37,200,000	33,600,000												
January	31	5.14	0.90				37,200,000	33,600,000	0	37,200,000	7,047,043	1,233,918	34,676,405	0	36,000,000	5,072,774	2,001,689	31,320,624	8,336,720	17,457,612
February	28	3.70	1.46				37,200,000	33,600,000	0	37,200,000	6,210,721	2,865,432	34,676,405	0	36,000,000	3,784,015	5,086,484	33,557,812	5,868,884	28,676,957
March	31	4.53	2.09				37,200,000	36,000,000	0	37,200,000	13,710	8,514,034	34,676,405	0	36,000,000	425,016	9,391,487	33,557,812	1,139,719	29,816,676
April	30	2.76	3.71				37,200,000	37,200,000	0	37,200,000	0	11,160,103	34,676,405	0	36,000,000	0	9,583,430	34,676,405	(6,524,283)	17,315,664
May	31	0.01	6.21				37,200,000	37,200,000	0	37,200,000	0	9,583,430	34,676,405	0	36,000,000	1,508,122	6,416,374	33,557,812	(2,466,064)	1,619,321
June	30	0.31	6.85				37,200,000	36,000,000	0	37,200,000	0	9,583,430	34,676,405	0	36,000,000	2,168,212	4,236,452	34,676,405	453,355	453,355
July	31	0.00	8.14				37,200,000	36,000,000	0	37,200,000	0	1,645,224	33,557,812	0	36,000,000	4,332,423	1,645,224	33,557,812	5,129,387	5,582,742
August	31	0.00	6.99				37,200,000	36,000,000	0	37,200,000	0	1,165,367	34,676,405	0	37,200,000	2,179,922	1,165,367	34,676,405	3,538,150	9,120,892
September	30	1.10	4.68				37,200,000	36,000,000	0	37,200,000	0	63,299,994	408,286,707	0	37,200,000	32,739,958	63,299,994	408,286,707	-846,743	9,120,892
October	31	1.58	3.09				37,200,000	36,000,000	0	37,200,000	0	32,739,958	408,286,707	0	37,200,000	0	32,739,958	408,286,707	-2,6	9,120,892
November	30	3.16	1.20				37,200,000	36,000,000	0	37,200,000	0	32,739,958	408,286,707	0	37,200,000	0	32,739,958	408,286,707	0	9,120,892
December	31	1.59	0.85				37,200,000	36,000,000	0	37,200,000	0	32,739,958	408,286,707	0	37,200,000	0	32,739,958	408,286,707	0	9,120,892
Total	365	23.88	46.17				1,344.2	1,344.2	0.0	1,344.2	100.5	194.3	1,253.0	0	438,000,000	32,739,958	63,299,994	408,286,707	-846,743	2,6

Total Area = 50.5 acres

Total (gal) = 1,344.2

Total (ac-ft) = 0.0

Total (gal) = 438,000,000

Total (ac-ft) = 1,344.2

Total (gal) = 32,739,958

Total (ac-ft) = 100.5

Total (gal) = 63,299,994

Total (ac-ft) = 194.3

Total (gal) = 408,286,707

Total (ac-ft) = 1,253.0

- 1/ Rainfall Data per the Western Regional Climate Center.
- 3/ Evaporation data per WRCC X.0.75
- 5/ Design Capacity Effluent Production
- 7/ Total existing wet area of the existing lagoons.
- 19/ Surface Rainfall = Volume of 100 Year rainfall on the existing WWTFF treatment and disposal ponds.
- 20/ Surface Evaporation = Volume of effluent and rain water evaporating from the existing WWTFF treatment and disposal ponds.
- 21/ Pond Percolation = Volume of effluent and rain water percolating into the ground for existing ponds. 1 through 8 plus proposed additional ponds.
- 23/ Required Storage = Theoretical starting point. Sept. 1st where pond storage starts at zero with monthly contributions.
- 36/ Maximum Storage Needed = Peak end of month pond storage volume needed (gallons & ac-ft).
- 37/ Storage Available from all ponds = Total volume of available storage.
- 39/ Check Balance = Comparison of this value with 15/.

Maximum Required storage	29,816,676
Total Storage Available ^{37/}	113,859,014 gal
Extra Storage ^{38/}	84,042,338 gal
Total Effluent Production ^{15/}	438,000,000 gal
Total Effluent Exported ^{17/}	0 gal
Total Surface Rainfall ^{19/}	32,739,958 gal
Total Evaporation ^{20/}	63,299,994 gal
Total Percolation ^{21/}	408,286,707 gal
Effluent Applied to Crop ^{28/}	0 gal
Check Balance ^{39/}	438,046,743 gal

Updated: 4/14/08
 Print Date: 7/25/08



Table 9
 Malaga County Water District
 Wastewater Treatment & Disposal Facilities
 1.65 MGD Capacity Wastewater Disposal - Average Year Rainfall Water Balance, Discharge and Storage

DATA:

Month	Number of Days per Month	Average Yr. Rainfall ^{1/} (in/month)	Average Yr. Evaporation ^{3/} (in/month)	Discharge to canal	MGD
January	31	2.11	0.98	0	0
February	28	1.91	1.58		
March	31	1.89	3.15		
April	30	1.00	4.73		
May	31	0.37	6.98		
June	30	0.15	8.55		
July	31	0.01	9.30		
August	31	0.01	8.03		
September	30	0.17	5.93		
October	31	0.53	3.75		
November	30	1.19	1.73		
December	31	1.58	0.90		
Total	365	10.92	55.61		

Month	Daily Effluent Production ^{5/} = Pond Wet Area = Pond Storage = Pond Percolation Rate =	MGD	Effluent Produced (gal/month)	Effluent To Canal (gal/month)	Effluent to Ponds ^{18/} (gal/month)	Surface Rainfall ^{19/} (gal/month)	Surface Evaporation ^{20/} (gal/month)	Pond Percolation ^{21/} (gal/month)	Monthly Change in Storage ^{22/} (gal/month)	Required Storage Capacity ^{23/} (gal)
January	23.24 acres 185.9 ac-ft 0.60 in/day		51,150,000	0	51,150,000	3,594,723	1,669,587	44,988,246	8,086,890	21,126,112
February			46,200,000	0	46,200,000	3,253,991	2,691,783	40,634,545	6,127,663	27,253,775
March			51,150,000	0	51,150,000	3,219,917	5,366,529	44,988,246	4,015,142	31,268,917
April			49,500,000	0	49,500,000	1,703,660	8,058,312	43,537,013	(391,665)	30,877,262
May	Additional Pond Wet Area = 39.50 acres Additional Pond Storage = 237.0 ac-ft Estimated Pond Percolation Rate = 1.00 in/day		51,150,000	0	51,150,000	630,354	11,891,547	44,988,246	(5,099,439)	25,777,813
June			49,500,000	0	49,500,000	255,549	14,566,293	43,537,013	(8,347,757)	17,430,056
July			51,150,000	0	51,150,000	17,037	15,844,038	44,988,246	(9,665,247)	7,764,809
August			51,150,000	0	51,150,000	17,037	13,680,390	44,988,246	(7,501,599)	263,210
September			49,500,000	0	49,500,000	289,622	10,102,704	43,537,013	(3,850,095)	0*
October			51,150,000	0	51,150,000	902,940	6,388,725	44,988,246	675,969	675,969
November			49,500,000	0	49,500,000	2,947,355	2,947,352	43,537,013	5,043,010	5,718,979
December			51,150,000	0	51,150,000	2,691,783	1,533,294	44,988,246	7,320,243	13,039,222
Total	Total Area = 62.7 acres		602,250,000	0	602,250,000	18,603,968	94,740,534	529,700,319	-3,586,885	Start at 0 Stored September 1st

WWTF POND CALCULATIONS:

1/ Rainfall Data per the Western Regional Climate Center.
 3/ Evaporation data per WRCC X 0.75
 5/ Average Daily Effluent Production
 7/ Total wet area of the existing lagoons.
 19/ Surface Rainfall = Volume of Average Year rainfall on the existing WWTF treatment and storage ponds and proposed storage ponds.
 20/ Surface Evaporation = Volume of effluent and rain water evaporating from the existing WWTF treatment and disposal ponds.
 21/ Pond Percolation = Volume of effluent and rain water percolating into the ground for existing ponds 1 through 8 plus additional proposed ponds.
 22/ Required Storage = Theoretical starting point Sept. 1st where pond storage starts at zero with monthly contributions.
 23/ Maximum Storage Needed = Peak end of month pond storage volume needed (gallons & ac-ft).
 37/ Storage Available from all ponds = Total volume of available storage
 39/ Check Balance = Comparison of this value with 18/.



Table 10
 Malaga County Water District
 Wastewater Treatment & Disposal Facilities
 1.65 MGD Capacity Wastewater Disposal - 100 Year Rainfall Water Balance, Discharge and Storage

WWTF POND CALCULATIONS:

Month	Number of Days per Month	100 Yr. Rainfall ^{1/} (in/month)	100 Yr. Evaporation ^{2/} (in/month)	Discharge to canal	0	MGD	Daily Effluent Production ^{5/} = 1,650,000 gpd	Pond Wet Area ⁷ = 23.24 acres	Pond Storage = 185.9 ac-ft	Pond Percolation Rate = 0.60 in/day	Additional Pond Wet Area = 43.00 acres	Additional Pond Storage = 258.0 ac-ft	Estimated Pond Percolation Rate = 1.00 in/day	Total Storage = 443.9 ac-ft	Total Storage = 144,851.976 gal	8 ft deep	8 ft deep	Effluent Produced (gal/month)	Effluent To Canal (gal/month)	Effluent to Ponds ^{18/} (gal/month)	Surface Rainfall ^{19/} (gal/month)	Surface Evaporation ^{20/} (gal/month)	Pond Percolation ^{21/} (gal/month)	Monthly Change in Storage ^{22/} (gal/month)	Required Storage Capacity ^{23/} (gal)
January	31	5.14	0.90															51,150,000	0	51,150,000	9,245,318	1,618,830	47,934,486	10,842,002	22,525,270
February	28	3.70	1.46															46,200,000	0	46,200,000	6,655,190	2,626,102	43,295,695	6,933,423	29,458,693
March	31	4.53	2.09															51,150,000	0	51,150,000	8,148,111	3,759,283	47,934,486	7,604,342	37,063,035
April	30	2.76	3.71															49,500,000	0	49,500,000	4,964,412	6,673,177	46,388,213	1,403,022	38,466,057
May	31	0.01	6.21															51,150,000	0	51,150,000	17,987	11,169,927	47,934,486	(7,936,426)	30,529,631
June	30	0.31	6.85															49,500,000	0	49,500,000	557,597	12,321,095	46,388,213	(8,651,711)	21,877,920
July	31	0.00	8.14															51,150,000	0	51,150,000	0	14,641,418	47,934,486	(11,425,904)	10,452,016
August	31	0.00	6.99															51,150,000	0	51,150,000	17,987	12,572,913	47,934,486	(9,357,399)	1,094,617
September	30	1.10	4.68															49,500,000	0	49,500,000	1,978,570	8,417,916	46,388,213	(3,327,559)	0*
October	31	1.58	3.09															51,150,000	0	51,150,000	2,841,946	5,557,983	47,934,486	499,477	499,477
November	30	3.16	1.20															49,500,000	0	49,500,000	5,683,892	2,158,440	46,388,213	6,637,239	7,136,716
December	31	1.59	0.85															51,150,000	0	51,150,000	2,859,933	1,528,895	47,934,486	4,548,552	11,683,268
Total	365	23.88	46.17															602,250,000	0.0	602,250,000	42,952,956	83,045,979	564,389,919	-2,232,942	-6.9
Total Area = 66.2 acres															Total (ac-ft)	1,848.2	0.0	1,848.2	131.8	254.9	1,732.0	-2,232,942	September 1st		

1/ Rainfall Data per the Western Regional Climate Center.
 2/ Evaporation data per WRCO X 0.75
 3/ Design Capacity Effluent Production
 7/ Total existing wet area of the existing lagoons.
 19/ Surface Rainfall = Volume of 100 Year rainfall on the existing WWTF treatment and storage ponds and proposed storage ponds.
 20/ Surface Evaporation = Volume of effluent and rain water evaporating from the existing WWTF treatment and disposal ponds.
 21/ Pond Percolation = Volume of effluent and rain water percolating into the ground for existing ponds 1 through 8 plus proposed additional ponds.
 23/ Required Storage = Theoretical starting point Sept. 1st where pond storage starts at zero with monthly contributions.
 36/ Maximum Storage Needed = Peak end of month pond storage volume needed (gallons & ac-ft).
 37/ Storage Available from all ponds = Total volume of available storage.
 39/ Check Balance = Comparison of this value with 16/.

Maximum Required storage	38,466,057
Total Storage Available ^{37/}	144,851,976 gal
Extra Storage ^{38/}	106,185,919 gal
Total Effluent Production ^{18/}	602,250,000 gal
Total Effluent Exported ^{17/}	0 gal
Total Surface Rainfall ^{19/}	42,952,956 gal
Total Evaporation ^{20/}	83,045,979 gal
Total Percolation ^{21/}	564,389,919 gal
Effluent Applied to Crop ^{28/}	0 gal
Check Balance ^{39/}	604,482,942 gal



Table 11
Malaga County Water District
Wastewater Treatment & Disposal Facilities
Disposal Pond Acreage Required to Replace 0.45 MGD Discharge to Central Canal


WWTF POND CALCULATIONS:

Month	Number of Days per Month	Average Yr. Rainfall ^{1/} (in/month)	Average Yr. Evaporation ^{3/} (in/month)	Daily Effluent Production ^{5/} = Pond Wet Area = Pond Storage = Pond Percolation Rate =	8 ft deep	Effluent Produced (gal/month)	Effluent To Canal (gal/month)	Effluent to Ponds ^{6/} (gal/month)	Surface Rainfall ^{19/} (gal/month)	Surface Evaporation ^{20/} (gal/month)	Pond Percolation ^{21/} (gal/month)	Monthly Change in Storage ^{22/} (gal/month)	Required Storage Capacity ^{23/} (gal)
January	31	2.11	0.98	450,000 gpd		13,950,000	0	13,950,000	859,433	399,168	12,626,744	1,783,521	4,456,076
February	28	1.91	1.58			12,600,000	0	12,600,000	777,970	643,557	11,404,801	1,329,612	5,785,688
March	31	1.89	3.15			13,950,000	0	13,950,000	769,824	1,283,040	12,626,744	810,040	6,595,728
April	30	1.00	4.73			13,500,000	0	13,500,000	407,314	1,926,597	12,219,429	(238,712)	6,357,016
May	31	0.37	6.98	Additional Pond Wet Area = Additional Pond Storage = Estimated Pond Percolation Rate =	15.00 acres 90.0 ac-ft 1.00 in/day	13,950,000	0	13,950,000	150,706	2,843,054	12,626,744	(1,369,092)	4,987,924
June	30	0.15	8.55	Total Storage =	90.0 ac-ft 29,326,631 gal	13,500,000	0	13,500,000	61,097	3,482,537	12,219,429	(2,140,889)	2,847,055
July	31	0.01	9.30			13,950,000	0	13,950,000	4,073	3,788,023	12,626,744	(2,460,694)	386,361
August	31	0.01	8.03			13,950,000	0	13,950,000	4,073	3,270,734	12,626,744	(1,943,405)	0
September	30	0.17	5.93			13,500,000	0	13,500,000	69,243	2,415,374	12,219,429	(1,065,560)	0
October	31	0.53	3.75			13,950,000	0	13,950,000	215,877	1,527,429	12,626,744	11,704	11,704
November	30	1.19	1.73			13,500,000	0	13,500,000	484,704	704,654	12,219,429	1,060,621	1,072,325
December	31	1.58	0.90			13,950,000	0	13,950,000	643,557	366,583	12,626,744	1,600,230	2,672,555
Total	365	10.92	55.61			164,250,000	0	164,250,000	4,447,871	22,850,750	164,869,728	-2,622,664	2,672,555
				Total Area =	15.0 acres	504.1	0.0	504.1	136	69.5	456.3	-2,622,504	8.0

1/ Rainfall Data per the Western Regional Climate Center.
 3/ Evaporation data per WRCC X 0.75
 5/ Average Daily Effluent Production
 7/ Total wet area of the existing lagoons.
 19/ Surface Rainfall = Volume of Average-Year rainfall on the existing WWTF treatment and storage ponds and proposed storage ponds.
 20/ Surface Evaporation = Volume of effluent and rain water evaporating from the existing WWTF treatment and disposal ponds.
 21/ Pond Percolation = Volume of effluent and rain water percolating into the ground for existing ponds 1 through 9 plus additional proposed ponds.
 23/ Required Storage = Theoretical starting point Sept. 1st where pond storage starts at zero with monthly contributions.
 36/ Maximum Storage Needed = Peak end of month pond storage volume needed (gallons & ac-ft)
 37/ Storage Available from all ponds = Total volume of available storage.
 39/ Check Balance = Comparison of this value with 16/.

Maximum Required storage	6,595,728
Total Storage Available ^{37/}	29,326,631 gal
Extra Storage ^{38/}	22,730,903 gal
Total Effluent Production ^{16/}	164,250,000 gal
Total Effluent Exported ^{17/}	0 gal
Total Surface Rainfall ^{19/}	4,447,871 gal
Total Evaporation ^{20/}	22,650,750 gal
Total Percolation ^{21/}	148,669,725 gal
Effluent Applied to Crop ^{28/}	0 gal
Check Balance ^{39/}	166,872,604 gal





0 400 800 Feet



EST. 1968
PROVOST & PRITCHARD
 ENGINEERING GROUP
An Employee Owned Company



286 W. Cromwell Ave.
 Fresno, CA 93711-6162
 (559) 449-2700

Legend

-  Malaga CWD Boundary
-  Fresno Co. Parcel
-  Ag Preserve Parcel

Figure 2

Disposal Capacity Study
 Malaga CWD



PROVOST & PRITCHARD
 ENGINEERING GROUP
 286 W. Cromwell Ave.
 Fresno, CA 93711-6162
 (559) 449-2700


MALAGA COUNTY WATER DISTRICT

EXISTING ZONING
JULY 2008

Legend	
	Malaga CWD
	Served by the City of Fresno
	Canal
	Railroad
Fresno County Zoning	
	AE-5 / 95.1 Ac
	AL20 / 738.4 Ac
	C6 / 1.7 Ac
	CM / 0.9 Ac
	M1 / 6.4 Ac
	M3 / 456.0 Ac
	O / 14.3 Ac
	RA / 2.3 Ac

Figure 1

Zoning
Malaga CWD



48 HOURS
 BEFORE EXCAVATING
 CALL "U.S.A." TOLL FREE
 800 642-2444
 UNDERGROUND SERVICE
 ALERT

SOUTH MAPLE AVENUE

- NOTES APPLICABLE TO SHEETS 6 THROUGH 11
- ① INSTALL 45 BEND 10"x10" W/ THRUST BLOCK PER MOWD STD. DET. W-6
 - ② INSTALL 10" WATER VALVE AND BOX W/ TRAFFIC LID PER MOWD STD. DET. W-1
 - ③ INSTALL 10" PLUG UNDER
 - ④ INSTALL 10"x10" TEE W/ THRUST BLOCK PER MOWD STD. DET. W-6
 - ⑤ INSTALL 10" CROSS
 - ⑥ INSTALL 90° BEND 10"x10" W/ THRUST BLOCK PER MOWD STD. DET. W-6
 - ⑦ INSTALL 8" X 8" TEE W/ THRUST
 - ⑧ INSTALL 8" ASSEMBLY PER MOWD STD. DET. W-2
 - ⑨ PER MOWD STD. DET. W-3
 - ⑩ INSTALL BLOW OFF ASSEMBLY PER MOWD STD. DET. W-7
 - ⑪ INSTALL THE ROD PER DETAIL ON SHEET 50

RECORD DOCUMENT
 DATE: 4-5-94
 THE ENGINEER'S PROFESSIONAL SEAL AND SIGNATURE ARE REQUIRED ON ALL RECORD DOCUMENTS. THE ENGINEER'S SEAL AND SIGNATURE ARE REQUIRED ON ALL RECORD DOCUMENTS. THE ENGINEER'S SEAL AND SIGNATURE ARE REQUIRED ON ALL RECORD DOCUMENTS.



PROPOST & PRITCHARD
 ENGINEERS
 3580 SOMMIT PARK STREET, FRESNO, CALIFORNIA 93722
 PHONE (209) 486-7333 FAX (209) 486-7310


CONSTRUCTION OF WATER & SEWER IMPROVEMENTS - SOUTH MAPLE AVENUE

DATE: 4-5-94
 SHEET: 7 OF 62 SHEETS

MALAGA COUNTY WATER DISTRICT
 EDA AWARD No. 07-01-04039

FIGURE 4

DATE: 11/17/99
 DRAWN BY: J. B. BROWN
 CHECKED BY: J. B. BROWN
 PROJECT NO. 07-01-04039
 SHEET NO. 62 OF 62




48 HOURS
 BEFORE EXCAVATING
 CALL "U.S.A." TOLL FREE
 800 642-2444
 UNDERGROUND SERVICE
 ALERT

SOUTH MAPLE AVENUE

NOTE: CONTRACTOR SHALL VERIFY IN FIELD THE LOCATION OF ALL FROM DAMAGE

LEGEND:
 CITY
 COUNTY
 APPROXIMATE CITY/COUNTY LIMIT LINE

- NOTES: APPLICABLE TO SHEETS 6 THROUGH 11
- ① INSTALL 4\"/>



Note: Alignment reflects need to keep intersection open for traffic during construction. Construction ease next on east side property required for Jack and bore under inter section. Parliament 10ft diameter requires on east side property.




PROYOST & PRITCHARD
 ENGINEERS
 5800 SUTTER PARKWAY, SUITE 200, SAN FRANCISCO, CA 94121
 TEL: 415-774-1100 FAX: 415-774-1101

DESIGN ENGINEER: J. B. BROWN
 DATE: 11/17/99
 SHEET: 62 OF 62

MALAGA COUNTY WATER DISTRICT
 11+00 EDA AWARD No. 07-01-04039
 12+00

CONSTRUCTION OF WATER & SEWER IMPROVEMENTS - SOUTH MAPLE AVENUE TREATMENT PLANT TO STA 11+00



0 100 200
Feet



EST. 1988
PROVOST & PRITCHARD
ENGINEERING GROUP
AN ENGINEERING DESIGN FIRM
286 W. CROMWELL AVE.
FRESNO, CA 93711-6162
(559) 449-2700


Legend

- Existing Water Main
- Existing Sewer Main
- Fresno County Parcel

Figure 6

Disposal Alternatives
ADM and Calpine Property
Malaga CWD

Photography by AirPhoto USA, 2007



0 100 200 Feet



EST. 1988
PROVOST & PRITCHARD
 ENGINEERING GROUP
 286 W. Cromwell Ave.
 Fresno, CA 93711-6162
 (559) 449-2700

Legend

- Existing Water Main
- Existing Sewer Main
- Fresno County Parcel

Figure 7

Disposal Alternatives
 Community Park Property
 Malaga CWD

Photography by AirPhoto USA, 2007



EST. 1888
PROVOST & PRITCHARD
 ENGINEERING GROUP
AN ENGINEERING COMPANY
 286 W. Cromwell Ave.
 Fresno, CA 93711-6162
 (559) 449-2700


Legend

-  Existing Water Main
-  Existing Sewer Main
-  Fresno County Parcel

Figure 8

Disposal Alternatives
 Konkeli Property
 Malaga CWD

Photography by AirPhoto USA, 2007



0 100 200 Feet



EST. 1968
PROVOST & PRITCHARD
 ENGINEERING GROUP
An Employee Owned Company

286 W. Cromwell Ave.
 Fresno, CA 93711-6162
 (559) 449-2700



Legend

-  Existing Water Main
-  Existing Sewer Main
-  Fresno County Parcel

Figure 9

Disposal Alternatives
 PPG Property
 Malaga CWD

Photography by AirPhoto USA, 2007



EST. 1988
PROVOST & PRITCHARD
 ENGINEERING GROUP
AN FORTY-NINE YEAR COMPANY
 286 W. Cromwell Ave.
 Fresno, CA 93711-6162
 (559) 449-2700

Legend

- Existing Water Main
- Existing Sewer Main
- Fresno County Parcel


Figure 10

Disposal Alternatives
 Rio Bravo Property
 Malaga CWD

Photography by AirPhoto USA, 2007

FIGURE 11

DRAFT
Malaga County Water District
Short term Treatment and Disposal Facilities Improvement Schedule




APPENDIX

APPENDIX B

Master Plan of Wastewater Treatment Facilities

APPENDIX C

Preliminary Opinion of Cost for Disposal Facilities



PROCESS SCHEMATIC
N.T.S.

LEGEND
 _____ PROPOSED PROCESS LINE
 _____ PROPOSED AUXILIARY LINE
 _____ EXISTING PROCESS LINE

PLANT SCADA
 LOCATED IN ADMIN BUILDING

XXXXXXXXX
 OPEN CLOSE
 OPEN CLOSE
 TURBIDITY METER

LAMP FAILURE ALARM
 LAMP FAILURE ALARM
 HIGH TURBIDITY ALARM
 POWER FAILURE ALARM

ALARM HIGH PRIORITY
 ALARM LOW PRIORITY
 UV-1 OUTPUT
 BLANK
 UV-2 OUTPUT
 BLANK
 UV-3 OUTPUT
 BLANK
 EC SENSOR OUTPUT

UV PLC
 BY MANUFACTURER
 UV-304 UVS-300
 UVS-301 UVS-302

UV DISINFECTION

EC-305
 EC MONITORING

TSF-1
 55 GAL. DRUM (NIC)
 3/8" HYS
 1/4" CIS
 HYP-1
 55 GAL. DRUM (NIC)
 3/8" HYS
 HYDROCHLORIC STORAGE HPT
 CALCIUM HYPOCHLORITE STORAGE TST

307
 FLOW INDICATOR
 307
 COMPOSITE SAMPLER
 6" FTE
 4" SCD (E)
 TO HEADWORKS
 4" SCD (E)
 TO HEADWORKS
 ETM-1
 ETM-2
 6" FTE
 4" SCD (E)
 TO HEADWORKS
 8" FTE
 FID CANAL (E)
 6" FTE

PRELIMINARY
 NOT FOR CONSTRUCTION
 01/03/2007

COPYRIGHT 2007 by PROVOST & PRITCHARD ENGINEERING GROUP, INC. ALL RIGHTS RESERVED. THE FIRM OF PROVOST & PRITCHARD ENGINEERING GROUP, INC. EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT AND OTHER APPLICABLE PROPERTY RIGHTS IN THESE PLANS. THESE PLANS ARE NOT TO BE REPRODUCED, CHANGED, OR COPIED IN ANY FORM OR MANNER WHATSOEVER, NOR ARE THEY TO BE ASSIGNED TO A THIRD PARTY WITHOUT FIRST OBTAINING THE WRITTEN PERMISSION AND CONSENT OF PROVOST & PRITCHARD ENGINEERING GROUP, INC. IN THE EVENT OF UNAUTHORIZED REUSE OF THESE PLANS BY A THIRD PARTY, THE THIRD PARTY SHALL HOLD THE FIRM OF PROVOST & PRITCHARD ENGINEERING GROUP, INC. HARMLESS, AND SHALL BEAR THE COST OF PROVOST & PRITCHARD ENGINEERING GROUP, INC.'S LEGAL FEES ASSOCIATED WITH DEFENDING AND ENFORCING THESE RIGHTS.

EST. 1968
PROVOST & PRITCHARD
 ENGINEERING GROUP
 An Employee Owned Company
 266 WEST CROMWELL AVENUE
 FRESNO, CALIFORNIA 93711-6162
 559/449-2700 FAX 559/449-2715
 www.pengroup.com

MALAGA WWTP MODIFICATIONS
 WASTEWATER TREATMENT PLANT
 MALAGA COUNTY WATER DISTRICT
 FRESNO COUNTY
 UV DISINFECTION
 PROCESS AND INSTRUMENTATION

DESIGN ENGINEER
 MICHAEL TAYLOR
 LICENSE NO.

DRAWN BY: CHECKED BY:
 DWA






SCALE: AS SHOWN

DATE: 2-14-2008

JOB NO. 10370802

DWG. NO.


SHEET
 3 OF 13




A SECTION
21 N.T.S.

B SECTION
21 N.T.S.

C SECTION
21 N.T.S.



DETAIL A
N.T.S.



LEGEND

- EXISTING
- NEW
- WATER LINES
- HOSE BIBB
- GATE VALVES
- SPRAY NOZZLE
- NOTED
- 1. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 2. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 3. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 4. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 5. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 6. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 7. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 8. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 9. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 10. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 11. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 12. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 13. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 14. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 15. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 16. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 17. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 18. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 19. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 20. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER
- 21. DIVERSITY AND REPORT 1" PW AS REQUIRED TO CLARIFIER

PERMITS
DATE: 4-1-99
NO. 9910101



SCALE: 1/8"=1'-0"
16

NO. 07-01-04039

MALAGA COUNTY WATER DISTRICT

3580 SOUTH FRANK STREET, PERRIS, CALIFORNIA, 92570

CONSTRUCTION OF WATER & SEWER IMPROVEMENTS

PLANT WATER PIPING, SECTIONS & DETAILS

DESIGN ENGINEER: CE LICENSE NO. 9910101


DATE: 4-1-99

PROJECT NO. 07-01-04039


21

OF


62 SHEETS



PLAN
1/4"=1'-0"



SECTION A-A
1/2"=1'-0"



DETAIL A
1/2"=1'-0"

NOTE: REINFORCING BARS TO BE INSTALLED IN ALL CHANGING AND JOINTS WITH AN EXTERIOR FACE OF CHANNEL. REINFORCEMENT PINS NOT SHOWN.

RECORD DOCUMENT
DATE 4-7-94
FILE RECORD DOCUMENTS HAVE BEEN REVIEWED FOR CONFORMANCE WITH THE RECORD DOCUMENTS AND APPROVED FOR RECORD. THE DRAWING SHALL NOT BE REPRODUCED OR COPIED FOR ANY OTHER PROJECT WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER.

NOTE: SEE SPECIFICATIONS FOR ACCEPTABLE ALTERNATE DIFFUSERS.



EDA AWARD No. 07-01-04039

MALAGA COUNTY WATER DISTRICT
3450 SOUTH FRANK STREET, TRESTON, CALIFORNIA 92755
PHONE (949) 485-7353 FAX (949) 485-7318

CONSTRUCTION OF WATER & SEWER IMPROVEMENTS
WWT-1 - AERATION TANK PLAN & SECTIONS

DESIGN ENGINEER	DATE	SHEET
PROYOST & PRITCHARD	07/12/97	34
DATE REVISION	APPROVED	62
55-0182		



PROYOST & PRITCHARD
REGISTERED PROFESSIONAL ENGINEERS
CITY OF MALAGA
2000 W. 20TH ST. MALAGA, CA 92651
TEL: (949) 485-7353 FAX: (949) 485-7318

APPENDIX A

Design Criteria Summary

FIGURES

APPENDIX C

Preliminary Opinion of Cost for Disposal Facilities

TABLE 12

Malaga County Water District
Potential Disposal Sites

APN	Owner	Total Acreage	Pond Acreage
330 031 60S	Southern Pacific Pipe	13.8	10.9
330 031 42S	Southern Pacific Pipe	12.8	10.4
330 031 11	Sargenti	4.34	3.7
330 031 46S	Parnagian	53.7	33.0
330 031 45	Parnagian	27.9	24.0
330 021 20	Raco	18.4	13.5
330 021 18	TRICOZ	13.3	11.0

Treatment Plant Capacity	0.8 MGD	1.2 MGD	1.65 MGD
Additional Disposal Pond Acreage	13.25	27.25	43.00

Malaga County Water District

PRELIMINARY Estimate for Disposal Pond Expansion February, 2008

	Property	APN	330 031 42S	\$ 20,000	per Ac	Located in Maple Avenue	Located in Easements East of Maple	Located in Easements Adjacent to Railroad Tracks
Property						12.8 Ac	\$ 256,000	12.8 Ac \$ 256,000
Easements								
Permanent	\$ 20,000	per Ac				0.6 Ac	\$ 12,000	0.5 Ac \$ 10,000
Construction	\$ 10,000	per Ac				0.6 Ac	\$ 6,000	1.0 Ac \$ 10,000
Fencing	\$ 15	LF				3000 LF	\$ 45,000	3000 LF \$ 45,000
Pond Construction (Earthwork)	\$ 8	CY				42000 CY	\$ 336,000	42000 CY \$ 336,000
Piping to Property (Gravity Main) On WWTP Site Off WWTP Site	\$ 90	LF				3150 LF 600 2550	\$ 283,500	3535 LF \$ 318,150 1400 2135
Jack & Bore	\$ 350	LF				150 LF	\$ 52,500	75 LF \$ 26,250
Lift Station						LS	\$ 125,000	LS \$ 125,000
Gravel Surfacing						LS	\$ 100,000	LS \$ 100,000
Trench Resurfacing	\$ 25	LF				2400 LF	\$ 60,000	50 LF \$ 1,250
Electrical and Controls						LS	\$ 200,000	LS \$ 200,000
Traffic Control						LS	\$ 100,000	LS \$ 50,000
Environmental						LS	\$ 50,000	LS \$ 50,000
Planning						LS	\$ 50,000	LS \$ 50,000
Permitting						LS	\$ 50,000	LS \$ 50,000
Design and Construction Review						LS	\$ 300,000	LS \$ 300,000
Subtotal							\$ 2,060,755	\$ 1,973,500
Contingencies (30%)							\$ 618,226	\$ 592,050
Total							\$ 2,678,981	\$ 2,565,550

Note: This preliminary estimate is applicable only for APN 330 031 42S and does not include APN 330-031-605, APN 330-031-45S, APN 330-031-46S, APN 330-211-20, or APN 330-211-18, and is dependent on the property owners willingness to move forward. APN 330-031-42S could provide 10.5 acres of additional pond disposal, about 25% of the additional disposal area required for the ultimate 1.65 MGD capacity of the WWTP.