

Los Angeles Regional Water Quality Control Board

Si necesita información en español, por favor llame a Susana Lagudis, Participación Pública: 213-576-6694

NOTIFICATION OF WORK (July 2015) Geotechnical Investigation Carousel Tract and Surrounding Area

Under the direction of the Regional Water Quality Control Board, consultants hired by Shell Oil Products US will be performing geotechnical investigations in the Carousel neighborhood as part of the initial activities to support implementation of the approved Remedial Action Plan (RAP). Shell Oil Products US and its contractors will be contacting the owners and residents of the properties where the work will take place to answer questions and schedule this work.

WHERE: In the front yards of properties identified for excavation. A Table is attached showing the addresses where this work will be performed.

WHEN: Beginning on or about July 27, 2015

WHAT: The work involves using a track-mounted drilling rig to collect soil samples to either 10 or 20 feet below the ground surface at each location. A plug of grass from the lawn will be removed from the boring areas and set aside. After drilling is complete and the boreholes have been backfilled, the grass will be replaced to restore the lawn. As a safety measure and to protect against encountering underground utilities, Underground Services Alert will be contacted prior to starting the work.

A photo of a typical drilling rig is included. The drilling rig has a drive hammer that is used to drive the sampler into the ground and recover soil samples for testing. During short-term periods of up to approximately 5 minutes, elevated sound levels may occur in the vicinity of the rig.

For more information, please contact:
Dr. Teklewold Ayalew, Regional Board Project Manager
(213) 576-6739 Teklewold.Ayalew@waterboards.ca.gov

Susana Lagudis, Regional Board Public Participation
(213) 576-6694 susana.lagudis@waterboards.ca.gov

Roy Patterson, VP and Sr. Principal Geologist
AECOM: 714-433-7699 or 714-227-5924
roy.patterson@aecom.com

For project-related documents please visit:
<http://bit.do/kast>



Thank you for your patience and cooperation.

Planned addresses for Geotechnical work

Address	Street	Proposed Boring Depth
305	E. 244th Street	10 FT
321	E. 244th Street	10 FT
337	E. 244th Street	10 FT
357	E. 244th Street	10 FT
348	E. 248th Street	20 FT
360	E. 248th Street	20 FT
345	E. 249th Street	10 FT
348	E. 249th Street	10 FT
363	E. 249th Street	20 FT
377	E. 249th Street	20 FT
378	E. 249th Street	10 FT
412	E. 249th Street	10 FT
24406	MARBELLA	20 FT
24411	MARBELLA	10 FT
24512	MARBELLA	20 FT
24517	MARBELLA	10 FT
24606	MARBELLA	20 FT
24613	MARBELLA	10 FT
24616	MARBELLA	20 FT
24628	MARBELLA	20 FT
24703	MARBELLA	10 FT
24706	MARBELLA	20 FT
24716	MARBELLA	20 FT
24717	MARBELLA	10 FT
24733	MARBELLA	10 FT
24744	MARBELLA	10 FT
24402	NEPTUNE	20 FT
24409	NEPTUNE	20 FT
24503	NEPTUNE	20 FT
24508	NEPTUNE	20 FT
24518	NEPTUNE	20 FT
24522	NEPTUNE	20 FT
24523	NEPTUNE	20 FT
24603	NEPTUNE	20 FT
24613	NEPTUNE	20 FT
24622	NEPTUNE	20 FT
24629	NEPTUNE	20 FT
24703	NEPTUNE	20 FT

Address	Street	Proposed Boring Depth
24712	NEPTUNE	20 FT
24729	NEPTUNE	10 FT
24732	NEPTUNE	20 FT
24803	NEPTUNE	10 FT
24402	PANAMA	10 FT
24411	PANAMA	20 FT
24421	PANAMA	20 FT
24426	PANAMA	10 FT
24503	PANAMA	20 FT
24533	PANAMA	10 FT
24608	PANAMA	10 FT
24618	PANAMA	10 FT
24708	PANAMA	10 FT
24709	PANAMA	20 FT
24719	PANAMA	10 FT
24722	PANAMA	10 FT
24738	PANAMA	10 FT
24803	PANAMA	20 FT
24812	PANAMA	10 FT
24819	PANAMA	20 FT
24833	PANAMA	10 FT
24412	RAVENNA	20 FT
24416	RAVENNA	10 FT
24423	RAVENNA	10 FT
24426	RAVENNA	20 FT
24508	RAVENNA	20 FT
24509	RAVENNA	20 FT
24522	RAVENNA	20 FT
24609	RAVENNA	10 FT
24612	RAVENNA	10 FT
24706	RAVENNA	10 FT
24709	RAVENNA	20 FT
24719	RAVENNA	20 FT
24732	RAVENNA	10 FT
24739	RAVENNA	20 FT
24749	RAVENNA	20 FT
24752	RAVENNA	20 FT