Cachuma Project Water Rights Hearing

October 2003

Panel V

Presenter:

Ali Shahroody

Stetson Engineers

Water Supply Impacts

- Key Hydrologic Aspects of the Biological Opinion/Fish Management Plan
 - Instream Target Habitat Reaches
 - Variable Target Flows
 - Passage Release and Adaptive Management Accounts
 - Conjunctive use of Water Rights Releases
 - Ramping schedule for Water Rights Releases

Table 2- 1 Long-term Mainstem Rearing Target Flows

| Lake Cachuma Storage | Reservoir Spill? | Target Flow | Target Site |
|-------------------------|---|--------------------------------------|---------------------------------|
| > 120,000 AF | Spill > 20,000 AF | 10 cfs | Highway 154 Bridge |
| > 120,000 AF | Spill > 20,000 AF | 1.5 cfs* | Alisal Road Bridge |
| > 120,000 AF | If Spill is >20,000 AF in previous year | 1.5 cfs* | Alisal Road Bridge** |
| > 120,000 AF | Spill <20,000 AF or No Spill | 5 cfs | Highway 154 Bridge |
| < 120,000 AF | No Spill | 2.5 cfs | Highway 154 Bridge |
| <30,000 AF | No Spill | Periodic release; ≤30AF per month | Stilling Basin and Long Pool |

(Source: Lower Santa Ynez River Fish Management Plan, October 2, 2000, pg. 3-9)

^{*} When rainbow trout/steelhead are present in the Alisal Reach.

^{**} This target will be met in the year immediately following a > 20,000 AF spill year.

Project Capacity and Surcharge


- Original Cachuma Reservoir Capacity (750.0')
 205,000 AF
- 1989 Survey Capacity (750'): 190,400 AF
- 2000 Survey Capacity (750.0'): 188,000 AF
- Loss of Storage Capacity: 17,000 AF
- Cachuma Reservoir Surcharge


Table 2- 4 Cachuma Reservoir Surcharge


| Surcharge (feet) | Maximum Elevation (feet) | Maximum Storage (acre-feet) | Storage Difference from No Surcharge (acre-feet) | Maximum Surface Area (acres) |
|---------------------|--------------------------------|-----------------------------------|--|---------------------------------------|
| 0 | 750.0 | 188,035 | 0 | 3,048 |
| 0.75 | 750.75 | 190,336 | 2,301 | 3,076 |
| 1.8 | 751.8 | 193,585 | 5,550 | 3,113 |
| 3.0 | 753.0 | 197,343 | 9,308 | 3,155 |

Frequency of Flows Downstream of Cachuma Reservoir Under EIR Alternatives

- Releases at Bradbury Dam
- Flows at Hwy 154 Bridge
- Flows Above Alisal Bridge







Impacts of Fish Water Releases on Cachuma Project Water Supply

- Critical Drought Period (1949-1951)
- Real Time Management in Drought Period

Table 3- 1 Impacts of Fish Releases on Project Water Supply in Critical Drought Period,

1949 Through 1951 (acre-feet)

| EIR Alternative | Shortage in Critical Drought Year (1951) | Shortage as Percentage of Annual Draft | Cumulative Shortage in Critical Drought Period (1949-1951) | Shortage as Percentage of Annual Draft for Three Years |
|--------------------|---|---|--|--|
| 1 | 7,070 | 27 | 14,210 | 18% |
| 2 | 9,810 | 38 | 20,130 | 26% |
| 3A | 11,810 | 46 | 24,850 | 32% |
| 3B | 11,260 | 44 | 23,270 | 30% |
| 3C | 9,890 | 38 | 19,920 | 26% |
| 4A&B | 9,350 | 36 | 17,470 | 23% |

Note: Annual draft from Cachuma Project is 25,714 acre-feet.

Table 3- 2 Impacts of Fish Releases on Project Water Supply in Critical Drought Period, 1949 through 1951 With Reserves Set Aside for an Additional Dry Year

(acre-feet)

| EIR Alternative | Shortage in Critical Drought Year 1951 | Shortage as Percentage of Annual Draft | Cumulative Shortage in Critical Drought Period 1949-1951 | Shortage as Percentage of Annual Draft for Three Years |
|--------------------|--|--|--|--|
| 1 | 12,740 | 50 | 22,800 | 30% |
| 2 | 14,790 | 58 | 27,030 | 35% |
| 3A | 16,500 | 64 | 31,220 | 40% |
| 3B | 15,940 | 62 | 29,460 | 38% |
| 3C | 15,380 | 60 | 27,750 | 36% |
| 4A&B | 15,090 | 59 | 24,530 | 32% |

Note: Annual draft from Cachuma Project is 25,714 acre-feet.





Table 3- 4 Simulated Impacts to Water Right Releases for Water Years 1918-1993 (acre-feet/year)

| | Alt 1 | Alt 2 | Alt 3A | Alt 3B | Alt 3C | Alt 4 A&B |
|---------------------------------------|-------|-------|--------|--------|--------|--------------|
| WR89-18 Releases | 6,322 | 6,023 | 5,658 | 5,682 | 5,737 | 5,711 |
| Difference in WR89- 18 Releases | | -299 | -660 | -640 | -590 | -611 |
| Percent Reduction in WR89-18 Releases | | 4.7% | 10.4% | 10.1% | 9.3% | 9.7% |


Releases for the B.O. Long-Term Flow Requirements

- Releases from Cachuma Project
- Releases from WR89-18
- Leakage from the dam

Annual Releases to Meet Rearing Target Flows of 2.5/5/10 cfs at 154 Bridge; 1.5 cfs at Alisal in spill and year after; 2.0 cfs in Hilton Creek From Cachuma Project



Annual Releases to Meet Rearing Target Flows of 2.5/5/10 cfs at 154 Bridge; 1.5 cfs at Alisal in spill and year after; 2.0 cfs in Hilton Creek From WR89-18



Annual Releases to Meet Rearing Target Flows of 2.5/5/10 cfs at 154 Bridge; 1.5 cfs at Alisal in spill and year after; 2.0 cfs in Hilton Creek From Cachuma Project and WR89-18




Table 4- 1 Releases Meeting Long-Term Rearing Target Flows Hydrologic Period 1918-1993

| | Acre-Feet/Year |
|-----------------------|----------------|
| Project Releases | 2,185 |
| Water Rights Releases | 1,220 |
| Leakage from Dam | 500 |
| Total | 3,905 |

